



Allegato Manuale di Installazione

Ver. 1.1



Openstack Installation

Tests





Allegato Manuale di Installazione

Ver. 1.1

Stato del deliverable

Ver.	Data	Autore della modifica	Note	Validazione
1.0	15-11-2014	Marica Antonacci (INFN-BARI)	Prima Stesura	INFN, ALMAVIVA
1.1	24-12-2014	Marica Antonacci (INFN-BARI)	Test plan ampliato e riorganizzato; individuate 3 categorie di test: basic tests, nominal tests, failover/recovery tests.	INFN, ALMAVIVA

Reference Documents

ID	Title				
R1	[PRISMA] (https://github Guide)	Openstack .com/pon-prism		llation ack-Instal	Guide lation-
R2	[PRISMA] Implementation	Enterprise on Guide	laaS:	High-a	availability



Allegato Manuale di Installazione

Ver. 1.1

INDICE DEGLI ARGOMENTI

1.	INI	RODUCTION	4
2.	BAS	BIC SANITY TESTS	5
	2.1	Verify the Identity Service (Keystone)	5
	2.2	Verify the Image Service (Glance)	11
	2.3	Verify the Compute Service (Nova)	12
	2.4	Verify the Block Storage Service (Cinder)	18
	2.5	Verify the Networking Service (Neutron)	23
	2.6	Verify the services on the Compute Nodes	26
3.	END	O-TO-END (NOMINAL) TESTS	28
	3.1	Verify the User creation (only as admin) and authentication	28
	3.2	Verify the VM instantiation	31
	3.3	Verify the Volume creation and attachment	36
4.	FAIL	LOVER/RECOVERY TESTS	42
	4.1	Verify the Controller node failover	42
	4.2	Verify the Network node failover	47
	4.2	Verify the Network node failover	





Allegato Manuale di Installazione

Ver. 1.1

1. Introduction

This documents provides a plan of tests that can be run to check and verify the correct installation [R1, R2] of your Openstack infrastructure.

Three different categories of tests will be described:

- 1) **Basic Sanity Tests:** they include some basic health checks that verify the status of the services and, if applicable, the status of the connections towards critical components, like the database and/or to the message broker (AMQP server). Moreover, the correct functioning of the api servers is checked for all the Openstack services (Keystone, Glance, Nova, Cinder, Neutron, etc.) using the openstack CLI clients.
- 2) **Nominal Tests**: they include a set of functional tests that allow to verify the system behaviour under standard operational conditions.
 - All these tests use the basic Openstack services (Nova, Glance, Keystone, Cinder, Neutron, etc) and therefore it is important to check the status of these services before running the tests (that can be done using the series of basic sanity tests).
- 3) Failover/Recovery Tests: these tests ensure that the system can successfully failover and recover from fault conditions (e.g. hardware, software, or network malfunctions). In particular, the failover testing ensures that, for those deployments that implement the High-Availability of the Openstack services, the backup "node" properly "takes over" for the failed one with minimum downtime.

Note that the basic and nominal tests can be conducted on your Openstack installation both in case you have implemented the high-availabilty (HA) as described in [R2] and in case you have not enabled the HA option.





Ver. 1.1

2. Basic Sanity Tests

2.1 Verify the Identity Service (Keystone)

The following steps allow to verify the correct installation of the Openstack Identity Service:

1. if set, clear OS_SERVICE_TOKEN and OS_SERVICE_ENDPOINT environment variables:

\$ unset OS_SERVICE_TOKEN OS_SERVICE_ENDPOINT

2. Request an authentication token by using the admin user and the password you chose for that user:

\$ keystone --os-username=admin --os-password=\$ADMIN_PASS --os-auth-url=http://<controller_ip>:35357/v2.0 token-get

In response, you should receive a token paired with your **user ID**. This verifies that the Identity Service is running on the expected endpoint and that your user account is established with the expected credentials.

The expected output is shown hereafter:







Allegato Manuale di Installazione


+
Property
Value
+
+ +
expires
2014-11-11T17:12:03Z
id
MIIC8QYJKoZIhvcNAQcCoIIC4jCCAt4CAQExCTAHBgUrDgMCGjCCAUcGCSqGSIb3DQEHAaCCATgEggE0eyJhY2Nlc3MiOiB7InRva2VuIjogeyJpc3N1ZWRfYXQiOiAi
MjAxNC0xMS0xMVQxNjoxMjowMy4zMjE1NTIiLCAiZXhwaXJlcyI6ICIyMDE0LTExLTExVDE30jEy0jAzWiIsICJpZCI6ICJwbGFjZWhvbGRlciJ9LCAic2VydmljZUNhdAydriandardardardardardardardardardardardardard
GFsb2ciOiBbXSwgInVzZXIiOiB7InVzZXJuYW1lIjogImFkbWluIiwgInJvbGVzX2xpbmtzIjogW10sICJpZCI6ICI3NjliN2ZhZmQ2YzE0NWNjYjg2ODBlMzk4NzAyZjE0Z
iIsICJyb2xlcyI6IFtdLCAibmFtZSI6ICJhZG1pbiJ9LCAibWV0YWRhdGEi0iB7ImlzX2FkbWluIjogMCwgInJvbGVzIjogW119fX0xggGBMIIBfQIBATBcMFcxCzAJBgNVB
AYTAIVTMQ4wDAYDVQQIDAVVbnNldDE0MAwGA1UEBwwFVW5zZXQxDjAMBgNVBAoMBVVuc2V0MRgwFgYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBw
 YFKw4DAhowDQYJKoZIhvcNAQEBBQAEggEAFgI+R1fAQQSCqB9qkUt0T4RTNswsI1PnEY9f7zcb50GJJMB8nHXxhkRhtD0KiwkRnLDkeNsFzSgQd+YQ8HS09aaB
L8M5t2SWI+hr4ki2q8buEuRhgpW+ePGlI2LuUPW3F8968W-BVX5OwflHp+AYa3ROfl6T9XxWgesKL7DcMmDem1Uq5w90R3682m-





Allegato Manuale di Installazione

Ver. 1.1



3. Verify that authorization behaves as expected. To do so, request authorization on a tenant:

```
$ keystone --os-username=admin --os-password=$ADMIN_PASS --os-tenant-name=admin --os-auth-url=http://
<controller_ip>:35357/v2.0 token-get
```

In response, you should receive a token that includes the ID of the tenant that you specified. This verifies that your user account has an explicitly defined role on the specified tenant and the tenant exists as expected.

The expected output is shown hereafter:





Allegato Manuale di Installazione





Allegato Manuale di Installazione

mI00Tc4Nzk2ZjU0MjJk0WFjZGVjNjRkYTZhYWY1ZiIsICJyZWdpb24i0iAicm0yIiwgImludGVybmFsVVJMIjogImh0dHA6Ly9jbG91ZDAzLnJvbWEyLmluZm4uaXQ
60Dc3NC92Mi9hZmI00Tc4Nzk2ZjU0MjJk0WFjZGVjNjRkYTZhYWY1ZiIsICJpZCI6ICI00TcxNjlmMzAxMGI0ZmI3YTJk0DAzYWU5N2JkZjU2MCIsICJwdWJsaWNV
Ukwi0iAiaHR0cDovL2Nsb3VkMDMucm9tYTIuaW5mbi5pdDo4Nzc0L3YyL2FmYjQ5Nzg3OTZmNTQyMmQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5V
Ukwi0iAiaHR0cDovL2ljZWN0bC5sbmdzLmluZm4uaXQ6ODc3NC92Mi9hZmI0OTc4Nzk2ZjU0MjJkOWFjZGVjNjRkYTZhYWY1ZiIsICJyZWdpb24i0iAidGVzdHJlZ2
lvbiIsICJpbnRlcm5hbFVSTCI6ICJodHRw0i8vaWNlY3RsLmxuZ3MuaW5mbi5pdDo4Nzc0L3YyL2FmYjQ5Nzg3OTZmNTQyMmQ5YWNkZWM2NGRhNmFhZjVmIi
wgImlkIjogIjFhZTVhMDYyMDFkNDQ1YTE4YzAzMjMzYmQ2NGJhOTM3IiwgInB1YmxpY1VSTCI6ICJodHRwOi8vaWNlY3RsLmxuZ3MuaW5mbi5pdDo4Nzc0L3Y
yL2FmYjQ5Nzg3OTZmNTQyMmQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwi0iAiaHR0cDovL2JhcmktcmVnaW9uLWN0bC5iYS5pbmZuLml00jg3
NzQvdjIvYWZiNDk3ODc5NmY1NDIyZDlhY2RIYzY0ZGE2YWFmNWYiLCAicmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwi0iAiaHR0cDovL2JhcmktcmVnaW
9uLWN0bC5iYS5pbmZuLml00jg3NzQvdjIvYWZiNDk30Dc5NmY1NDIyZDlhY2RIYzY0ZGE2YWFmNWYiLCAiaWQi0iAi0TE20Dg5MGQ3NTMzNGY20ThjZmNh
MTgyZTM4ZmFlNWUiLCAicHVibGljVVJMIjogImh0dHA6Ly9iYXJpLXJlZ2lvbi1jdGwuYmEuaW5mbi5pdDo4Nzc0L3YyL2FmYjQ5Nzg3OTZmNTQyMmQ5YWNkZ
WM2NGRhNmFhZjVmIn0sIHsiY
tenant_id
afb4978796f5422d9acdec64da6aaf5f
user_id
13b300f990ec4826a23cd252089e6cad
+
+





Allegato Manuale di Installazione

Ver. 1.1

You can also set your --os-* variables in your environment to simplify command-line usage.

For the following tests, create an admin-openrc.sh file in your home directory, with the following content:

```
export OS_USERNAME=admin
export OS_PASSWORD=$ADMIN_PASS
export OS_TENANT_NAME=admin
export OS_AUTH_URL=http://<controller_ip>:35357/v2.0
```





Allegato Manuale di Installazione

Ver. 1.1

2.2 Verify the Image Service (Glance)

Preparation:

Set your --os-* variables in your environment:

\$ source admin-openrc.sh

The following steps allow to verify the correct installation of the Openstack Image Service:

1. Verify that the Glance API is correctly configured and working:

```
$ glance image-list
```

If you have not uploaded any image yet, the output of this command will show an empty table; otherwise you will get the list of registered images.

2. Verify that the Glance registry process is working correctly by importing the Cirros image available online:

```
$ wget http://cdn.download.cirros-cloud.net/0.3.2/cirros-0.3.2-x86_64-disk.img
$ glance image-create --name "cirros-0.3.2-x86_64" --disk-format qcow2 --container-format bare --is-public
True --progress < cirros-0.3.2-x86_64-disk.img</pre>
```

3. Check the status of the image using the ID returned by the previous command:

\$ glance image-show <image_id>





Allegato Manuale di Installazione

Ver. 1.1

2.3 Verify the Compute Service (Nova)

Preparation:

Set your --os-* variables in your environment:

\$ source admin-openrc.sh

The following steps allow to verify the correct installation of the Openstack Compute Service:

1. Verify that all nova processes are up and running:

\$ for s in /etc/init.d/nova-*; do status \$(basename \$s); done

The expected output is like the following:

nova-api start/running, process 26601

nova-cert start/running, process 26615

nova-conductor start/running, process 26625

nova-consoleauth start/running, process 26659

nova-novncproxy start/running, process 26669

nova-scheduler start/running, process 26643

If one or more of the above processes are stopped, look at the log files in the folder /var/log/nova in order to find the problem.

2. To verify your configuration, list available images:





Allegato Manuale di Installazione

Ver. 1.1

\$ nova image-list

The output should be like this:

- 3. Verify the process "nova-cert" is running and connected to the database and messaging server (AMQP):
 - a. Verify the connection with the database (replace the DB_PORT value with the correct value depending on your installation. Default is 3306)

```
# export DB_PORT=3306
# netstat -punt | grep -s $DB_PORT | grep -s $(pgrep nova-cert)
```

The expected output shows the ESTABILISHED connection:

tcp 0 0 192.168.22.205:39263 192.168.205.99:33306 **ESTABLISHED** 23311/python





Allegato Manuale di Installazione

Ver. 1.1

b. Verify the connection with the messaging server (replace the AMQP_PORT value with the correct value depending on your installation. Default is 5672)

```
# export AMQP_PORT=5672
# netstat -punt | grep -s $AMQP_PORT | grep -s $(pgrep nova-cert)
```

The expected output shows the ESTABILISHED connection:

tcp	0	0 192.168.22.205:52498	192.168.22.68:5672	ESTABLISHED 23311/python	
-----	---	------------------------	--------------------	--------------------------	--

- 4. Verify the process "nova-scheduler" is running and connected to the database and messaging server (AMQP):
 - a. Verify the connection with the database (replace the DB_PORT value with the correct value depending on your installation. Default is 3306)

```
# export DB_PORT=3306
# netstat -punt | grep -s $DB_PORT | grep -s $(pgrep nova-scheduler)
```

The expected output shows the ESTABILISHED connections:

tcp	0	0 192.168.22.205:39303	192.168.205.99:33306	ESTABLISHED 23943/python
tcp	0	0 192.168.22.205:39355	192.168.205.99:33306	ESTABLISHED 23943/python





Allegato Manuale di Installazione

Ver. 1.1

b. Verify the connection with the messaging server (replace the AMQP_PORT value with the correct value depending on your installation. Default is 5672)

```
# export AMQP_PORT=5672
# netstat -punt | grep -s $AMQP_PORT | grep -s $(pgrep nova-scheduler)
```

The expected output shows the ESTABILISHED connections:

tcp	0	0 192.168.22.205:52528	192.168.22.68:5672	ESTABLISHED 23943/python
tcp	0	0 192.168.22.205:53220	192.168.22.68:5672	ESTABLISHED 23943/python

- 5. Verify the process "nova-consoleauth" is running and connected to the database and messaging server (AMQP):
 - a. Verify the connection with the database (replace the DB_PORT value with the correct value depending on your installation. Default is 3306)

```
# export DB_PORT=3306
# netstat -punt | grep -s $DB_PORT | grep -s $(pgrep -f /usr/bin/nova-consoleauth)
```

The expected output shows the ESTABILISHED connections:





Allegato Manuale di Installazione

Ver. 1.1

top 0 172:100:22:203:37237 172:100:203:77:33300 201:102:2012 233327 py chon	tcp	0	0 192.168.22.205:39257	192.168.205.99:33306	ESTABLISHED 23532/python	
--	-----	---	------------------------	----------------------	--------------------------	--

b. Verify the connection with the messaging server (replace the AMQP_PORT value with the correct value depending on your installation. Default is 5672)

```
# export AMQP_PORT=5672
# netstat -punt | grep -s $AMQP_PORT | grep -s $(pgrep -f /usr/bin/nova-consoleauth)
```

The expected output shows the ESTABILISHED connections:

tcp	0	0 192.168.22.205:43638	192.168.22.68:5672	ESTABLISHED 23532/python
tcp	0	0 192.168.22.205:52524	192.168.22.68:5672	ESTABLISHED 23532/python
tcp	0	0 192.168.22.205:52696	192.168.22.68:5672	ESTABLISHED 23532/python
tcp	0	0 192.168.22.205:53833	192.168.22.68:5672	ESTABLISHED 23532/python

6. Verify the process "nova-novnc" is running and listening on its port (default is 6080):

```
# netstat -a | grep -s 6080
```





Allegato Manuale di Installazione

Ver. 1.1

The expected output is like the following:

tcp 0 0 preprod-01.ba.infn:6080 *:* LISTEN	
--	--





Allegato Manuale di Installazione

Ver. 1.1

2.4 Verify the Block Storage Service (Cinder)

Preparation:

Set your --os-* variables in your environment:

\$ source admin-openrc.sh

The following steps allow to verify the correct installation of the Openstack Block Storage Service:

1. Verify that all cinder processes are up and running:

\$ for s in /etc/init.d/cinder-*; do status \$(basename \$s); done

The expected output is like the following:

cinder-api start/running, process 30050
cinder-scheduler start/running, process 30087
cinder-volume start/running, process 30127

If one or more of the above processes are stopped, look at the log files in the folder /var/log/cinder in order to find the problem. Note: depending on your installation, the cinder-volume process may not be running on the controller node (if you have decided to deploy it on a dedicated host, you should check its status there: ssh <cinder-host> service cinder-volume status).

7. Verify the process "cinder-scheduler" is running and connected to the database and messaging server (AMQP):





Allegato Manuale di Installazione

Ver. 1.1

a. Verify the connection with the database (replace the DB_PORT value with the correct value depending on your installation. Default is 3306)

```
# export DB_PORT=3306
# netstat -punt | grep -s $DB_PORT | grep -s $(pgrep -f /usr/bin/cinder-scheduler)
```

The expected output shows the ESTABILISHED connections:

tcp	0	0 192.168.22.205:45718	192.168.205.99:33306	ESTABLISHED 23943/python	
tcp	0	0 192.168.22.205:45812	192.168.205.99:33306	ESTABLISHED 23943/python	

b. Verify the connection with the messaging server (replace the AMQP_PORT value with the correct value depending on your installation. Default is 5672)

```
# export AMQP_PORT=5672
# netstat -punt | grep -s $AMQP_PORT | grep -s $(pgrep -f /usr/bin/cinder-scheduler)
```

The expected output shows the ESTABILISHED connections:

tcp	0	0 192.168.22.205:52528	192.168.22.68:5672	ESTABLISHED 23943/python	
tcp	0	0 192.168.22.205:53220	192.168.22.68:5672	ESTABLISHED 23943/python	





Allegato Manuale di Installazione

Ver. 1.1

8. Finally, to verify that cinder is configured properly, create a new volume:

\$ cinder create --display-name test 1

The expected output is like the following:

+		+-		-+
1	Property		Value	1
+		-+-		-+
1	attachments		[]	
	availability_zone		nova	
I	bootable	I	false	
I	created_at	I	2014-06-22T01:14:02.705154	
I	display_description	I	None	
I	display_name	I	test	
I	encrypted	1	False	
I	id	1	ad2f9004-3939-4b1c-a234-8ab26b8fe961	
1	metadata	I	{}	1
1	size	1	1	1





Allegato Manuale di Installazione

Ver. 1.1

	snapshot_id		None		
	source_volid	-	None		
	status	1	creating		
	volume_type	1	None	1	
+		-+		-+	

9. Check the volume status using the command "cinder list". The status should pass from "creating" to "available":

\$ cinder list

The expected output is like the following:

+		++	+		+	+	
+							
l ID	Ctatua	Display Name	l Ciro l	Volumo	Mrrno Doo	table Att	aghad
	Status	Display Name	s Size	vorume	туре воо	table Att	ached
to							
+		+			+	+	
+							
ad2f9004-3939-4b1c-a234-8ab26b8fe961	available	test	1	1	None	false	
dd217004-3737-4B1C-d234-0dB20B01C701	available	l cepe	1 +	1	None	Tuise	1
cfe55712-5933-42fe-b9a2-aacaa8620cd6	creating	test	1	1	None	false	
	, sidesing	1 0000	' -		2,3110	1 14150	





Allegato Manuale di Installazione

Ver. 1.1

Γ	+	_+	+	+	 +
	,				 ,
	+				
	'				

If the status value is not available, the volume creation failed. Check the log files in the /var/log/cinder/ directory on the controller and volume nodes to get information about the failure.





Allegato Manuale di Installazione

Ver. 1.1

2.5 Verify the Networking Service (Neutron)

Preparation:

Set your --os-* variables in your environment:

\$ source admin-openrc.sh

The following steps allow to verify the correct installation of the Openstack Networking Service. In this guide we assume that the networking services have been deployed onto a dedicated node (network node); therefore the following commands should be issued on the network node.

1. Verify that all neutron processes are up and running:

\$ for s in /etc/init.d/neutron-*; do status \$(basename \$s); done

The expected output is like the following:

neutron-dhcp-agent start/running, process 7515
neutron-13-agent start/running, process 7529
neutron-metadata-agent start/running, process 7537
neutron-ovs-cleanup start/running
neutron-plugin-openvswitch-agent start/running, process 7812
neutron-server start/running, process 7820

If one or more of the above processes are stopped, look at the log files in the folder /var/log/neutron in order to find the problem.





Allegato Manuale di Installazione

Ver. 1.1

2. Query the neutron API to get the list of networks:

```
$ neutron net-list
```

The expected output shows the list of the available networks (if any).

- 3. Verify the process "neutron-dhcp-agent" is running and connected to the messaging server (AMQP):
 - a. replace the AMQP PORT value with the correct value depending on your installation. Default is 5672

```
# export AMQP_PORT=5672
# netstat -punt | grep -s $AMQP_PORT | grep -s $(pgrep -f /usr/bin/neutron-dhcp-agent)
```

The expected output shows the ESTABILISHED connections:

tcp	0	0 192.168.22.218:47911	192.168.22.68:5672	ESTABLISHED 14058/python	
tcp	0	0 192.168.22.218:47912	192.168.22.68:5672	ESTABLISHED 14058/python	
tcp	0	0 192.168.22.218:47910	192.168.22.68:5672	ESTABLISHED 14058/python	

- 4. Verify the process "neutron-l3-agent" is running and connected to the messaging server (AMQP):
 - b. replace the AMQP_PORT value with the correct value depending on your installation. Default is 5672

```
# export AMQP_PORT=5672
```





Allegato Manuale di Installazione

Ver. 1.1

# netstat -punt grep -s \$AMQP_PORT	grep -s \$(pgrep -f /usr/bin/neutron-13-agent)
---------------------------------------	--

The expected output shows the ESTABILISHED connections:

tcp	0	0 192.168.22.218:46892	192.168.22.69:5672	ESTABLISHED 9986/python
tcp	0	0 192.168.22.218:47843	192.168.22.68:5672	ESTABLISHED 9986/python
tcp	0	0 192.168.22.218:46891	192.168.22.69:5672	ESTABLISHED 9986/python





Allegato Manuale di Installazione

Ver. 1.1

2.6 Verify the services on the Compute Nodes

Check that the compute and networking agents are up and running and able to communicate with the controller. Use the commands "nova service-list" and "neutron agent-list" (they can be issued from the controller node).

1. Load the admin credentials:

```
$ source admin-openrc.sh
```

2. verify that all the compute nodes are up:

```
$ nova service-list | grep nova-compute
```

nova-compute	preprod-05 nova	enabled up	2014-11-10T12:30:30.000000 None	
nova-compute	preprod-03 nova	enabled up	2014-11-17T15:49:45.000000 None	1
nova-compute	preprod-04 nova	enabled up	2014-11-17T22:48:51.000000 None	

3. verify that the neutron open-vswitch agent is running on the compute nodes:

```
$ neutron agent-list | grep vSwitch
```

The output shows ":-)" if the service is working fine or "xxx" if there are problems

156c	9d5-f685-450a-8fef-1bf9ca3c1e0f	Open	vSwitch a	agent	preprod-05	:-)	True	
30fa	dbc-7ae5-4f84-b11c-b8908544c7af	Open	vSwitch a	agent	preprod-04	:-)	True	





Allegato Manuale di Installazione

df7f0820-24d1-41e6-82db-fec1e3296af5 Open vSwitch agent preprod-03 :-)	True	
ed2a74b3-f246-44dd-a3f4-d1170e30b3c0 Open vSwitch agent preprod-02 :-)	True	1





Allegato Manuale di Installazione

Ver. 1.1

3. End-to-End (Nominal) Tests

3.1 Verify the User creation (only as admin) and authentication

The following bash script can be used to check that the installed Openstack infrastructure is able to provide basic user management functions.

To execute the script you must fill the variables at the beginning of the file with proper values depending on your installation.

#!/bin/bash
######################################
BEFORE RUNNING THIS SCRIPT FILL THE
FOLLOWING VARIABLES WITH PROPER VALUES
#####################################
export OS_USERNAME=admin #do not change this. Only admin can create users
export OS_PASSWORD= <password></password>
export OS_TENANT_NAME=admin
export OS_AUTH_URL=http:// <controller_ip>:35357/v2.0</controller_ip>
#####################################
##############





Allegato Manuale di Installazione

```
MAIN
 ###########################
if [ $# -ne 0 ]; then
                                       echo "Usage: ./`basename $0`"
                                       echo -e "\nThis probe tries to create a user and then tries to get a token using the user credentials.\nExit
code: 0 - probe successfully run; 1 - probe failed"
                                       exit 1
fi
TENANT ID=(\text{keystone tenant-create } --\text{name testenant} | \text{sed } -\text{n} | 
keystone tenant-list | grep -q -s $TENANT ID
if [ $? -ne 0 ]; then
                    echo "Some error occurred while creating tenant"
                    exit 1
else
                    echo "Tenant testenant ($TENANT ID) successfully created"
```





Allegato Manuale di Installazione

```
fi
USER ID=(\text{keystone user-create } --\text{name tesuser } --\text{tenant-id } TENANT ID --pass 12qwas | sed -n 's/^|\ \+id\ \+|\ \+\([^\
].*\)\ \+|/\1/p')
keystone user-list | grep -q -s $USER ID
if [ $? -ne 0 ]; then
   echo "Some error occurred while creating user"
   exit 1
else
   echo "User tesuser ($USER ID) successfully created"
fi
keystone --os-tenant-id $TENANT ID --os-username tesuser --os-password 12qwas token-qet | grep -q -s user id
if [ $? -ne 0 ]; then
   echo "Some error occurred during authentication of user tesuser ($USER ID) in tenant testenant ($TENANT ID)"
   exit 1
```





Allegato Manuale di Installazione

Ver. 1.1

echo "User tesuser (\$USER_ID) successfully authenticated in tenant testenant (\$TENANT_ID)"

fi

echo Cleaning env

keystone user-delete \$USER_ID && echo "user deleted successfully" || (echo "Error deleting user tesuser" && exit 1)

keystone tenant-delete \$TENANT_ID && echo "tenant deleted successfully" || (echo "Error deleting tenant testenant" && exit 1)

3.2 Verify the VM instantiation

The following bash script can be used to check that the installed Openstack infrastructure is able to provide running virtual machines.

To execute the script you must fill the variables at the beginning of the file with proper values depending on your installation.

IMAGE ID

To set the IMAGE_ID variable you can use the command "glance image-list" to list the available image ids.

FLAVOR_ID

To set the FLAVOR variable you can use the command "nova flavor-list" to list the available flavors (both the flavor name and id can be used).





Allegato Manuale di Installazione

Ver. 1.1

KEY_NAME

To set the KEY_NAME variable you can use the command "nova keypair-list" to list the available keypairs

NET_ID

To set the NET_ID variable you can use the command "neutron net-list" to list the available networks.





Allegato Manuale di Installazione

```
export NET ID=<network id>
LOOP THRESH=5
WAIT TIMEOUT=30
wait vm active()
{
   typeset vmid=$1
   let i=0
   status=
   while [ $i -lt $LOOP_THRESH -a "$status" != active ]
   do
       let i++
       status=$(nova show $vmid | awk '/OS-EXT-STS:vm_state/{print $4}')
       echo "VM status is <$status>"
       [ "$status" = active ] && continue
       sleep 30
   done
```





Allegato Manuale di Installazione

```
[ "$status" = active ]
############################
### MAIN
#############################
if [ $# -ne 0 ]; then
      echo "Usage: ./`basename $0`"
      echo -e "\nThis probe tries to create a new VM.\nExit code: 0 - probe successfully run (vm is active); 1 - probe
failed"
      exit 1
fi
#create the test VM
VM_ID=$(nova boot --image $IMAGE_ID --key-name $KEY_NAME --flavor $FLAVOR --nic net-id=$NET_ID test-vm | sed -n 's/^|\
\+id\ \+|\ \+\([^\ ].*\)\ \+|/\1/p')
echo "VM id is <$VM ID>"
# wait for vm to become active
wait vm active $VM ID
```





Allegato Manuale di Installazione

```
# check status
if [ $? -ne 0 ]; then
      echo "Error: instance not running after $LOOP_THRESH x $WAIT_TIMEOUT [sec]"
      exit code=1
else
      echo "OK. VM creation was successful"
      exit_code=0
fi
# terminate instance
nova delete $VM_ID
#return 0 if test is ok, 1 otherwise
exit $exit_code
```





Allegato Manuale di Installazione

Ver. 1.1

3.3 Verify the Volume creation and attachment

The following bash script can be used to check that the installed Openstack infrastructure is able to provide on-demand block devices to be attached to the running VMs. The component in charge of providing block storage functionalities is called "Cinder".

To execute the script you must fill the variables at the beginning of the file with proper values depending on your installation.





Allegato Manuale di Installazione

```
wait_volume_available()
    typeset volid=$1
   let i=0
    status=
   while [ $i -lt $LOOP THRESH -a "$status" != available ]
    do
        let i++
        status=$(cinder show $volid | awk '/ status /{print $4}')
        echo "Volume status is <$status>"
        [ "$status" = available ] && continue
        sleep 3
    done
    [ "$status" = available ]
```



PRISMA – PiattafoRme cloud Interoperabili per SMArt-government

PON04a2_A -PON04a2_A / F- Settore mart Cities and Communities and Social Innovation



Allegato Manuale di Installazione

```
wait_volume_in_use()
    typeset volid=$1
    let i=0
    status=
   while [ $i -lt $LOOP THRESH -a "$status" != in-use ]
    do
        let i++
        status=$(cinder show $volid | awk '/ status /{print $4}')
        echo "Volume status is <$status>"
        [ "$status" = in-use ] && continue
        sleep 3
    done
    [ "$status" = in-use ]
```





Allegato Manuale di Installazione

```
############################
### MAIN
if [ $# -gt 1 ]; then
     echo "Usage: ./`basename $0` [<instance-id>]"
     echo -e "\nThis probe tries to create a volume and (optional) attach it to the input instance, if provided.\nExit
code: 0 - probe successfully run; 1 - probe failed"
      exit 1
fi
VOL_ID=\$(cinder\ create\ 1\ |\ sed\ -n\ 's/^|\ \ +id\ \ +|\ \ +([^\ ].*\) \ \ +|/\1/p')
wait_volume_available $VOL_ID
```





Allegato Manuale di Installazione

```
# check status
if [ $? -ne 0 ]; then
      echo "Error: volume not available yet"
      exit 1
else
      echo "OK. Volume creation was successful (ID=$VOL ID)"
fi
if [ ! -z $1 ]; then
      echo Trying to attach volume $VOL ID to instance $1
      nova volume-attach $1 $VOL_ID | grep -q -s device && echo "OK" || (echo ERROR && exit 1)
      wait volume in use $VOL ID
      if [ $? -ne 0 ]; then
            echo ERROR while attaching volume
      else
            echo Volume successfully attached
```





Allegato Manuale di Installazione

```
fi

echo Trying to detach volume $VOL_ID from instance $1

nova volume-detach $1 $VOL_ID && echo "OK" || (echo ERROR && exit 1)

fi

echo Trying to delete volume

cinder delete $VOL_ID && echo "OK" || (echo ERROR && exit 1)
```





Allegato Manuale di Installazione

Ver. 1.1

4. Failover/Recovery Tests

Assumption: the Openstack infrastructure has been set-up implementing the high-availability as described in [R2].

4.1 Verify the Controller node failover

To verify that controller node HA is working, simply shut down the node hosting the controller services: you can power-off the host or you can simulate the host failure, as described below.

You should see the controller services group start on the other node.

1. Check the cluster status using the command "crm status":

```
root@controller-01:~# crm status

==========

Last updated: Tue Dec 23 21:53:07 2014

Last change: Tue Dec 16 16:16:14 2014 via crmd on controller-02

Stack: openais

Current DC: controller-01 - partition with quorum

Version: 1.1.6-9971ebba4494012a93c03b40a2c58ec0eb60f50c

3 Nodes configured, 3 expected votes

23 Resources configured.
```





Allegato Manuale di Installazione

```
_____
Online: [ controller-01 controller-02 controller-03 ]
Resource Group: q controller
    controller p vip (ocf::heartbeat:IPaddr2):
                                                   Started controller-01
    controller pub vip (ocf::heartbeat:IPaddr2):
                                                   Started controller-01
                 (ocf::heartbeat:apache):
                                              Started controller-01
    p apache
    p glance-registry (ocf::openstack:glance-registry): Started controller-01
    p glance-api (ocf::openstack:glance-api): Started controller-01
    p nova api (ocf::openstack:nova-api):
                                             Started controller-01
    p nova cert (ocf::openstack:nova-cert): Started controller-01
    p nova consoleauth (ocf::openstack:nova-consoleauth): Started controller-01
    p nova novnc (ocf::openstack:nova-novnc): Started controller-01
    p nova scheduler (ocf::openstack:nova-scheduler):
                                                         Started controller-01
    p cinder-api (ocf::openstack:cinder-api): Started controller-01
    p cinder-scheduler (ocf::openstack:cinder-schedule): Started controller-01
Resource Group: g network
```





Allegato Manuale di Installazione

Ver. 1.1

```
network_p_vip (ocf::heartbeat:IPaddr2): Started controller-03

network_pub_vip (ocf::heartbeat:IPaddr2): Started controller-03

p_neutron-server (ocf::openstack:neutron-server): Started controller-03

p_neutron-agent-13 (ocf::openstack:neutron-agent-13): Started controller-03

p_neutron-metadata-agent (ocf::openstack:neutron-metadata-agent): Started controller-03

p_neutron-dhcp-agent (ocf::openstack:neutron-agent-dhcp): Started controller-03
```

2. Shutdown the current controller node (controller-01 in our case). You can use the command "crm node standby" to put a node in standby mode. Note that any node in standby mode is no longer eligible to host resources and any resources that are there must be moved. Therefore, this can be used to simulate a node shutdown.

```
root@controller-01:~# crm node standby controller-01
```

3. You will see the controller services migrating from controller-01 to controller-02:

```
root@controller-01:~# crm status

========

Last updated: Tue Dec 23 22:14:13 2014

Last change: Tue Dec 23 22:14:11 2014 via crm_attribute on controller-01
```





Allegato Manuale di Installazione

```
Stack: openais
Current DC: controller-02 - partition with guorum
Version: 1.1.6-9971ebba4494012a93c03b40a2c58ec0eb60f50c
3 Nodes configured, 3 expected votes
23 Resources configured.
_____
Node controller-01: standby
Online: [ controller-02 controller-03 ]
Resource Group: q controller
     controller p vip (ocf::heartbeat:IPaddr2):
                                                   Started controller-02
     controller pub vip (ocf::heartbeat:IPaddr2):
                                                   Started controller-02
                                              Started controller-02
                 (ocf::heartbeat:apache):
    p apache
     p glance-registry (ocf::openstack:glance-registry): Started controller-02
     p glance-api (ocf::openstack:glance-api): Started controller-02
    p nova api (ocf::openstack:nova-api):
                                              Started controller-02
    p nova cert (ocf::openstack:nova-cert): Started controller-02
```





Allegato Manuale di Installazione

Ver. 1.1

```
p nova consoleauth (ocf::openstack:nova-consoleauth): Started controller-02
    p nova novnc (ocf::openstack:nova-novnc): Started controller-02
    p nova scheduler (ocf::openstack:nova-scheduler):
                                                         Started controller-02
    p cinder-api (ocf::openstack:cinder-api): Started controller-02
    p cinder-scheduler (ocf::openstack:cinder-schedule): Started controller-02
Resource Group: q network
                      (ocf::heartbeat:IPaddr2):
                                                   Started controller-03
    network p vip
                      (ocf::heartbeat:IPaddr2):
                                                   Started controller-03
    network pub vip
    p neutron-server (ocf::openstack:neutron-server):
                                                         Started controller-03
    p neutron-agent-13 (ocf::openstack:neutron-agent-13): Started controller-03
    p neutron-metadata-agent (ocf::openstack:neutron-metadata-agent): Started controller-03
    p neutron-dhcp-agent
                            (ocf::openstack:neutron-agent-dhcp):
                                                                     Started controller-03
```

- 4. Verify that all the services are active and running properly. Re-run the sanity checks described in section 2 and the functional tests in section 3.
- 5. Restore the node by removing the standby attribute from it: the node will become a fully active member of the cluster again:

root@controller-01:~# crm node online controller-01





Allegato Manuale di Installazione

Ver. 1.1

4.2 Verify the Network node failover

To verify that network node HA is working, simply shut down the node hosting the network node services: you can power-off the host or you can simulate the node shutdown.

You should see the network node services group start on the other node.

1. Check the cluster status using the command "crm status":





Allegato Manuale di Installazione

```
Resource Group: q controller
    controller p vip (ocf::heartbeat:IPaddr2):
                                                   Started controller-01
    controller pub vip (ocf::heartbeat:IPaddr2):
                                                   Started controller-01
    p apache
                (ocf::heartbeat:apache):
                                             Started controller-01
    p glance-registry (ocf::openstack:glance-registry): Started controller-01
    p glance-api (ocf::openstack:glance-api): Started controller-01
    p nova api (ocf::openstack:nova-api):
                                             Started controller-01
    p nova cert (ocf::openstack:nova-cert): Started controller-01
    p nova consoleauth (ocf::openstack:nova-consoleauth): Started controller-01
    p nova novnc (ocf::openstack:nova-novnc): Started controller-01
    p nova scheduler (ocf::openstack:nova-scheduler):
                                                         Started controller-01
    p cinder-api (ocf::openstack:cinder-api): Started controller-01
    p cinder-scheduler (ocf::openstack:cinder-schedule): Started controller-01
Resource Group: g network
    network p vip
                      (ocf::heartbeat:IPaddr2):
                                                   Started controller-03
                      (ocf::heartbeat:IPaddr2):
                                                   Started controller-03
    network pub vip
    p neutron-server
                      (ocf::openstack:neutron-server):
                                                         Started controller-03
    p neutron-agent-13 (ocf::openstack:neutron-agent-13): Started controller-03
```





Allegato Manuale di Installazione

Ver. 1.1

p_neutron-metadata-agent (ocf::openstack:neutron-metadata-agent): Started controller-03
p_neutron-dhcp-agent (ocf::openstack:neutron-agent-dhcp): Started controller-03

6. Shutdown the current controller node (controller-03 in our case). You can use the command "crm node standby" to put a node in standby mode. Note that any node in standby mode is no longer eligible to host resources and any resources that are there must be moved. Therefore, this can be used to simulate the node failure as described below.

root@controller-01:~# crm node standby controller-03

7. You will see the network node services migrating from controller-03 to controller-02:

```
root@controller-01:~# crm status

========

Last updated: Tue Dec 23 22:45:13 2014

Stack: openais

Current DC: controller-02 - partition with quorum

Version: 1.1.6-9971ebba4494012a93c03b40a2c58ec0eb60f50c

3 Nodes configured, 3 expected votes

23 Resources configured.
```





Allegato Manuale di Installazione

```
_____
Node controller-03: standby
Online: [ controller-02 controller-01 ]
Resource Group: q controller
    controller p vip (ocf::heartbeat:IPaddr2):
                                                   Started controller-01
    controller pub vip (ocf::heartbeat:IPaddr2):
                                                   Started controller-01
                                              Started controller-01
    p apache
                 (ocf::heartbeat:apache):
    p glance-registry (ocf::openstack:glance-registry): Started controller-01
    p glance-api (ocf::openstack:glance-api): Started controller-01
    p nova api (ocf::openstack:nova-api): Started controller-01
    p nova cert (ocf::openstack:nova-cert): Started controller-01
    p nova consoleauth (ocf::openstack:nova-consoleauth): Started controller-01
    p nova novnc (ocf::openstack:nova-novnc): Started controller-01
    p nova scheduler (ocf::openstack:nova-scheduler): Started controller-01
    p cinder-api (ocf::openstack:cinder-api): Started controller-01
    p cinder-scheduler (ocf::openstack:cinder-schedule): Started controller-01
```





Allegato Manuale di Installazione

Ver. 1.1

```
Resource Group: g_network

network_p_vip (ocf::heartbeat:IPaddr2): Started controller-02

network_pub_vip (ocf::heartbeat:IPaddr2): Started controller-02

p_neutron-server (ocf::openstack:neutron-server): Started controller-02

p_neutron-agent-13 (ocf::openstack:neutron-agent-13): Started controller-02

p_neutron-metadata-agent (ocf::openstack:neutron-metadata-agent): Started controller-02

p_neutron-dhcp-agent (ocf::openstack:neutron-agent-dhcp): Started controller-02
```

- 8. Verify that all the services are active and running properly. Re-run the sanity checks described in section 2 and the functional tests in section 3.
- 9. Restore the node by removing the standby attribute from it: the node will become a fully active member of the cluster again:

root@controller-01:~# crm node online controller-03