




Allegato Manuale di Installazione

Ver.



Openstack Installation

Basic Tests





Allegato Manuale di Installazione

Ver.

INDICE DEGLI ARGOMENTI

1.	VERIFY THE IDENTITY SERVICE (KEYSTONE)	3
2.	VERIFY THE IMAGE SERVICE (GLANCE)	9
3.	VERIFY THE COMPUTE SERVICE (NOVA)	10
4.	VERIFY THE BLOCK STORAGE SERVICE (CINDER)	16
5.	VERIFY THE NETWORKING SERVICE (NEUTRON)	21
6.	VERIFY THE SERVICES ON THE COMPUTE NODES	24
7.	END-TO-END TEST: VM INSTANTIATION	26





Allegato Manuale di Installazione

Ver.

1. Verify the Identity Service (Keystone)

The following steps allow to verify the correct installation of the Openstack Identity Service:

1. if set, clear OS_SERVICE_TOKEN and OS_SERVICE_ENDPOINT environment variables:

\$ unset OS_SERVICE_TOKEN OS_SERVICE_ENDPOINT

2. Request an authentication token by using the admin user and the password you chose for that user:

\$ keystone --os-username=admin --os-password=\$ADMIN_PASS --os-auth-url=http://<controller_ip>:35357/v2.0 token-get

In response, you should receive a token paired with your **user ID**. This verifies that the Identity Service is running on the expected endpoint and that your user account is established with the expected credentials.

The expected output is shown hereafter:

++





Allegato Manuale di Installazione

Property
Value
++
+
expires
2014-11-11T17:12:03Z
id
MIIC8QYJKoZIhvcNAQcCoIIC4jCCAt4CAQExCTAHBgUrDgMCGjCCAUcGCSqGSIb3DQEHAaCCATgEggE0eyJhY2Nlc3MiOiB7InRva2VuIjogeyJpc3N1ZWRfYXQiOiAinceAller
MjAxNC0xMS0xMVQxNjoxMjowMy4zMjE1NTIiLCAiZXhwaXJlcyI6ICIyMDE0LTExLTExVDE30jEy0jAzWiIsICJpZCI6ICJwbGFjZWhvbGRlciJ9LCAic2VydmljZUNhdAydrifichter and the standard of the standa
GFsb2ciOiBbXSwgInVzZXIiOiB7InVzZXJuYW1lIjogImFkbWluIiwgInJvbGVzX2xpbmtzIjogW10sICJpZCI6ICI3NjliN2ZhZmQ2YzE0NWNjYjg2ODBlMzk4NzAyZjE0ZhZmQ2YzE0ZhZmQ2YzE0NWNjYjg2ODBlMzk4NzAyZjE0ZhZmQ2YzE0ZhZmQ2YzE0NWNjYjg2ODBlMzk4NzAyZjE0ZhZmQ2YzE0ZhZmQ2YzE0ZhZmQ2YzE0ZhZmQ2YzE0NWNjYjg2ODBlMzk4NzAyZjE0ZhZmQ2YzE0ZhZmQ2ZhZmQ
iIs ICJy b 2x lcy I 6IFt d LCA ibmFtZSI 6ICJhZG1 pbiJ9LCA ibWV0 YWRhdGE iO iB7 ImlzX2 FkbWluIjogMCwgInJvbGVzIjogW119fX0 xggGBMIIBfQIBATBcMFcxCzAJBgNVBA properties and the properties of the p
AYTAIVTMQ4wDAYDVQQIDAVVbnNldDEOMAwGA1UEBwwFVW5zZXQxDjAMBgNVBAoMBVVuc2V0MRgwFgYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhhbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhbbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhbbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAYDVQQDDA93d3cuZXhbbXBsZS5jb20CAQEwBwArdAlvTMQ4wDAyDAyAlvTMQ4wDAyDAyAlvTMQ4wAyAlvTMQ4wAyAlvTMQ4wAyAlvTMQ4wAyAlvTMQ4wAyAlvTMQ4wAyAlvTMQ4wAyAlvTMQ4wAyAlvTMQ4wAyAlvTMQ4wAyAlvTMQ4wAyAyAyAyAyAyAyAyAyAyAyAyAyAyAyAyAyAyAy
YFKw4DAhowDQYJKoZIhvcNAQEBBQAEggEAFgI+R1fAQQSCqB9qkUt0T4RTNswsI1PnEY9f7zcb50GJJMB8nHXxhkRhtD0KiwkRnLDkeNsFzSgQd+YQ8HS09aaBullender and the state of the state o
L8M5t2SWI+hr4ki2q8buEuRhgpW+ePGlI2LuUPW3F8968W-BVX5OwflHp+AYa3ROfl6T9XxWgesKL7DcMmDem1Uq5w9OR3682m-
n4NYAcewkiDPPoj+NRkEmpRZdQVDm9vtitp-RPMcySXW7KSiWzSOD1AbqK7Ug5mh1PSSGAb7LRg8fQ-
w8+ZQMnVpks+uqObNc7MuFqhlIK1PTe1oFLS2YwCp4BtrbWD8xu0dVRchiLpFzcFwBVNnXuC47KA==





Allegato Manuale di Installazione





Allegato Manuale di Installazione

+
Property
Value
+
+
expires
2014-11-18T03:04:05Z
id
MIIrygYJKoZIhvcNAQcCoIIruzCCK7cCAQExCTAHBgUrDgMCGjCCKqMGCSqGSIb3DQEHAaCCKpQEgiqQeyJhY2Nlc3MiOiB7InRva2VuIjogeyJpc3N1ZWRfYXQiOiAi
MjAxNC0xMS0xOFQwMDowNDowNS40MzI1MzciLCAiZXhwaXJlcyI6ICIyMDE0LTExLTE4VDAzOjA00jA1WiIsICJpZCI6ICJwbGFjZWhvbGRlciIsICJ0ZW5hbnQi0indian and the company of the
B7 ImRlc2 NyaXB0 aW9 uljog IiIsICJlbmFibGVkIjog dHJ1ZSwg ImlkIjog ImFmYjQ5 Nzg3 OTZmNTQyMmQ5 YWNkZWM2 NGRhNmFhZjVmIiwg Im5hbWUiOiAiYWR table to the control of the contro
W4ifX0slCJzZXJ2aWNlQ2F0YWxvZyI6IFt7ImVuZHBvaW50cyI6IFt7ImFkbWluVVJMIjogImh0dHA6Ly9jbG91ZDAzLnJvbWEyLmluZm4uaXQ60Dc3NC92Mi9hZ
mI00Tc4Nzk2ZjU0MjJk0WFjZGVjNjRkYTZhYWY1ZiIsICJyZWdpb24i0iAicm0yIiwgImludGVybmFsVVJMIjogImh0dHA6Ly9jbG91ZDAzLnJvbWEyLmluZm4uaXQ
6ODc3NC92Mi9hZmI0OTc4Nzk2ZjU0Mj]kOWFjZGVjNjRkYTZhYWY1ZiIsICJpZCI6ICI0OTcxNjlmMzAxMGI0ZmI3YTJkODAzYWU5N2JkZjU2MCIsICJwdWJsaWNV
UkwiOiAiaHR0cDovL2Nsb3VkMDMucm9tYTIuaW5mbi5pdDo4Nzc0L3YyL2FmYjQ5Nzg3OTZmNTQyMmQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5V
ominion of the control of the contro





Allegato Manuale di Installazione

Ukwi OiA ia HR 0 c DovL2 ljZWN 0 b C 5 s bmdz Lmlu Zm 4 ua XQ 6 O D c 3 N C 9 2 Mi 9 h Zm I 0 O T c 4 Nzk 2 ZjU 0 MjJk 0 W FjZGVjNjRkYTZhYWY 1 ZiIs I C JyZW dpb 2 4 i OiA id GVzdHJlZ 2 C MjZ N C S S S S S S S S S S S S S S S S S S
lvbiIsICJpbnRlcm5hbFVSTCI6ICJodHRw0 i8vaWNlY3RsLmxuZ3MuaW5mbi5pdDo4Nzc0L3YyL2FmYjQ5Nzg3OTZmNTQyMmQ5YWNkZWM2NGRhNmFhZjVmIndelited for the compact of the co
wg Imlk Ijog IjFhZTVhMDYyMDFkNDQ1YTE4YzAzMjMzYmQ2NGJhOTM3 Iiwg InB1YmxpY1VSTCI6IC JodHRwOi8vaWNlY3RsLmxuZ3MuaW5mbi5pdDo4Nzc0L3YndAvarantee and the state of the property of
y L2 FmYjQ5Nzg3OTZmNTQyMmQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uLWN0bC5iYS5pbmZuLml0Ojg3Nzg3OTZmNTQyMmQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uLWN0bC5iYS5pbmZuLml0Ojg3Nzg3OTZmNTQyMmQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uLWN0bC5iYS5pbmZuLml0Ojg3Nzg3OTZmNTQyMmQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uLWN0bC5iYS5pbmZuLml0Ojg3Nzg3OTZmNTQyMmQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uLWN0bC5iYS5pbmZuLml0Ojg3Nzg3OTZmNTQyMmQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uLWN0bC5iYS5pbmZuLml0Ojg3Nzg3OTZmNTQyMnQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uLWN0bC5iYS5pbmZuLml0Ojg3Nzg3OTZmNTQyMnQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uLWN0bC5iYS5pbmZuLml0Ojg3Nzg3OTZmNTQyMnQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uLWN0bC5iYS5pbmZuLml0Ojg3Nzg3OTZmNTQyMnQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwiOiAiaHR0cDovL2JhcmhQyMnQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwiOiAiaHR0cDovL2JhcmhQyMnQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwiOiAiaHR0cDovL2JhcmhQyMnQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwiOiAiaHR0cDovL2JhcmhQyMnQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWRtaW5VUkwiOiAiaHR0cDovL2JhcmhQyMnQ5YWNkZWM2NGRhNmFhZjVmIn0sIHsiYWNAMAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAA
NzQvdjIvYWZiNDk3ODc5NmY1NDIyZDlhY2RIYzY0ZGE2YWFmNWYiLCAicmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmkiLCAiaW50ZXJuYWxVUkwiOiAiaHR0cDovL2JhcmktcmVnaW9uIjogImJhcmktcmVnaW9uIjogImJhcmktcmVnaW9uIjogImJhcmktcmVnaW9uIjogImJhcmktcmVnaW9uIjogImJhcmktcmVnaW9uIjogImJhcmktcmVnaW9uIjogImJhcmktmVnaW9uIjogImJhcmktmVnaW9uIjogImJhcmktmVnaW9uIjogImJhcmktmVnaW9uIjogImJhcmktmVnaW9uIjogImJhcmktmVnaW9uIjogImJhcmktmVnaW9uIjogImJhcmktmVnaW9uIjogImJhcmktmVnaW9uIjogImJhcmktmVnaW9uIjogImJhcmktmVnaW9uIjogImJhcmktmVnaW9uIjogImJhcmktmVnaW9uIjogImJhcmktmVnaW9uIjogImJhcmktmVnaW0uIjogImJhcmktmVnaW0uIjogImJhcmktmVnaW0uIjogImJhcmktmVnaW0uIjogImJhcmktmVnaW0uIjogImJhcmktmVnaW0uIjogImJhcmktmVnaW0uIjogImJhcmktmVnaW0uIjogImJhcmktmVnaW0uIjogImJhcmktmVnaW0uIjogImJhcmktmVnaW0uIjogImJhcmktmVnaW0uIjogImJhcmktmW0uIjogImJhcmktmVnaW0uIjogImJhcmktmVnaW0uIjogImJhcmktmW0uIjogImJhcmktmVnaW0uIjogImJhcmktmVnaW0uIjogImJhcmktmW0uIjogImJhcmktmW0uIjogImJhcmktmW0uIjogImJhcmktmW0uIjogImJhcmktmW0uIjogImJhcmktmW0uIjogImJhcmktmW0uIjogImJhcmktmW0uIjogImJhcmktmW0uIijogImJhcmhtmW0uIijogImJhcmhtmW0uIijogImJhcmhtmW0uIijogImJhcmhtmW0uIijogImJhcmhtmW0uIijogImJhcmhtmW0uIijogImJhcmhtmW0uIijogImJhcmhtmW0uIijogImJhcmhtmW0uIijogImJhcmhtmW0uIijogImJhcmhtmW0uIijogImJhcmhtmW0uIijogImJhc
9 u LWN0 b C5 i YS5 p b m Z u Lm l00 j g3 Nz Qvdj IvYWZ i NDk3 ODc5 NmY1 NDIyZDlhY2 RlYzY0 ZGE2 YWFmNWY i LCA i aWQi0 i AiOTE2 ODg5 MGQ3 NTMzNGY2 OThjZmNh2 NDIYZDlhY2 RlYzY0 ZGE2 YWFmNWY i LCA i aWQi0 i AiOTE2 ODg5 MGQ3 NTMzNGY2 OThjZmNh2 NDIYZDlhY2 RlYzY0 ZGE2 YWFmNWY i LCA i aWQi0 i AiOTE2 ODg5 MGQ3 NTMzNGY2 OThjZmNh2 NDIYZDlhY2 RlYzY0 ZGE2 YWFmNWY i LCA i aWQi0 i AiOTE2 ODg5 MGQ3 NTMzNGY2 OThjZmNh2 NDIYZDlhY2 RlYzY0 ZGE2 YWFmNWY i LCA i aWQi0 i AiOTE2 ODg5 MGQ3 NTMzNGY2 OThjZmNh2 NDIYZDlhY2 RlYzY0 ZGE2 YWFmNWY i LCA i aWQi0 i AiOTE2 ODg5 MGQ3 NTMzNGY2 OThjZmNh2 NDIYZDlhY2 RlYzY0 ZGE2 YWFmNWY i LCA i aWQi0 i AiOTE2 ODg5 MGQ3 NTMZNGY2 OThjZmNh2 NDIYZDlhY2 RlYZY0 ZGE2 YWFmNWY i LCA i aWQi0 i AiOTE2 ODg5 MGQ3 NTMZNGY2 OThjZmNh2 NDIYZDlhY2 RlYZY0 ZGE2 YWFmNWY i LCA i aWQi0 i AiOTE2 ODg5 MGQ3 NTMZNGY2 OThjZmNh2 NDIYZDlhY2 RlYZY0 ZGE2 YWFmNWY i LCA i aWQi0 i AiOTE2 ODg5 MGQ3 NTMZNGY2 OThjZmNh2 NDIYZDlhY2 RlYZY0 ZGE2 YWFmNWY i LCA i aWQi0 i AiOTE2 ODg5 MGQ3 NTMZNGY2 OThjZmNh2 NDIYZDlhY2 RlYZY0 ZGE2 YWFmNWY i LCA i aWQi0 i AiOTE2 ODg5 MGQ3 NTMZNGY2 OThjZmNh2 NDIYZDlhY2 RlYZY0 ZGE2 YWFmNWY i LCA i aWQi0 i AiOTE2 ODg5 MGQ3 NTMZNGY2 OThjZmNh2 NDIYZDlhY2 RlYZY0 ZGE2 YWFmNWY i LCA i aWQi0 i AiOTE2 ODg5 MGQ3 NTMZNGY2 OThjZmNh2 NDIYZDlhY2 NDIYZD
MTgyZTM4ZmFlNWUiLCAicHVibGljVVJMIjogImh0dHA6Ly9iYXJpLXJlZ2lvbi1jdGwuYmEuaW5mbi5pdDo4Nzc0L3YyL2FmYjQ5Nzg3OTZmNTQyMmQ5YWNkZM12PmV12PmV12PmV12PmV12PmV12PmV12PmV12PmV
WM2NGRhNmFhZjVmIn0sIHsiY
tenant_id
afb4978796f5422d9acdec64da6aaf5f
user_id
13b300f990ec4826a23cd252089e6cad
+





Allegato Manuale di Installazione

Ver.

You can also set your --os-* variables in your environment to simplify command-line usage.

For the following tests, create an admin-openrc.sh file in your home directory, with the following content:

```
export OS_USERNAME=admin
export OS_PASSWORD=$ADMIN_PASS
export OS_TENANT_NAME=admin
export OS_AUTH_URL=http://<controller_ip>:35357/v2.0
```





Allegato Manuale di Installazio

Ver

2. Verify the Image Service (Glance)

Preparation:

Set your --os-* variables in your environment:

```
$ source admin-openrc.sh
```

The following steps allow to verify the correct installation of the Openstack Image Service:

1. Verify that the Glance API is correctly configured and working:

```
$ glance image-list
```

If you have not uploaded any image yet, the output of this command will show an empty table; otherwise you will get the list of registered images.

2. Verify that the Glance registry process is working correctly by importing the Cirros image available online:

```
$ wget http://cdn.download.cirros-cloud.net/0.3.2/cirros-0.3.2-x86_64-disk.img
$ glance image-create --name "cirros-0.3.2-x86_64" --disk-format qcow2 --container-format bare --is-public
True --progress < cirros-0.3.2-x86_64-disk.img</pre>
```

3. Check the status of the image using the ID returned by the previous command:

```
$ glance image-show <image_id>
```





Allegato Manuale di Installazio

ν	e	r	

3. Verify the Compute Service (Nova)

Preparation:

Set your --os-* variables in your environment:

```
$ source admin-openrc.sh
```

The following steps allow to verify the correct installation of the Openstack Compute Service:

1. Verify that all nova processes are up and running:

```
$ for s in /etc/init.d/nova-*; do status $(basename $s); done
```

The expected output is like the following:

```
nova-api start/running, process 26601
nova-cert start/running, process 26615
nova-conductor start/running, process 26625
nova-consoleauth start/running, process 26659
nova-novncproxy start/running, process 26669
nova-scheduler start/running, process 26643
```

If one or more of the above processes are stopped, look at the log files in the folder /var/log/nova in order to find the problem.

2. To verify your configuration, list available images:





Allegato Manuale di Installazione

Ver.

\$ nova image-list

The output should be like this:

- 3. Verify the process "nova-cert" is running and connected to the database and messaging server (AMQP):
 - a. Verify the connection with the database (replace the DB_PORT value with the correct value depending on your installation. Default is 3306)

```
# export DB_PORT=3306
# netstat -punt | grep -s $DB_PORT | grep -s $(pgrep nova-cert)
```

The expected output shows the ESTABILISHED connection:

tcp 0 0 192.168.22.205:39263 192.168.205.99:33306 **ESTABLISHED** 23311/python





Allegato Manuale di Installazione

Ver.

b. Verify the connection with the messaging server (replace the AMQP_PORT value with the correct value depending on your installation. Default is 5672)

```
# export AMQP_PORT=5672
# netstat -punt | grep -s $AMQP_PORT | grep -s $(pgrep nova-cert)
```

The expected output shows the ESTABILISHED connection:

tcp	0	0 192.168.22.205:52498	192.168.22.68:5672	ESTABLISHED 23311/python	
-----	---	------------------------	--------------------	--------------------------	--

- 4. Verify the process "nova-scheduler" is running and connected to the database and messaging server (AMQP):
 - a. Verify the connection with the database (replace the DB_PORT value with the correct value depending on your installation. Default is 3306)

```
# export DB_PORT=3306
# netstat -punt | grep -s $DB_PORT | grep -s $(pgrep nova-scheduler)
```

The expected output shows the ESTABILISHED connections:

tcp	0	0 192.168.22.205:39303	192.168.205.99:33306	ESTABLISHED 23943/python
tcp	0	0 192.168.22.205:39355	192.168.205.99:33306	ESTABLISHED 23943/python





Allegato Manuale di Installazione

Ver.

b. Verify the connection with the messaging server (replace the AMQP_PORT value with the correct value depending on your installation. Default is 5672)

```
# export AMQP_PORT=5672
# netstat -punt | grep -s $AMQP_PORT | grep -s $(pgrep nova-scheduler)
```

The expected output shows the ESTABILISHED connections:

tcp	0	0 192.168.22.205:52528	192.168.22.68:5672	ESTABLISHED 23943/python
tcp	0	0 192.168.22.205:53220	192.168.22.68:5672	ESTABLISHED 23943/python

- 5. Verify the process "nova-consoleauth" is running and connected to the database and messaging server (AMQP):
 - a. Verify the connection with the database (replace the DB_PORT value with the correct value depending on your installation. Default is 3306)

```
# export DB_PORT=3306
# netstat -punt | grep -s $DB_PORT | grep -s $(pgrep -f /usr/bin/nova-consoleauth)
```

The expected output shows the ESTABILISHED connections:





Allegato Manuale di Installazione

Ver.

tcp	0	0 192.168.22.205:39257	192.168.205.99:33306	ESTABLISHED 23532/python	
-----	---	------------------------	----------------------	--------------------------	--

b. Verify the connection with the messaging server (replace the AMQP_PORT value with the correct value depending on your installation. Default is 5672)

```
# export AMQP_PORT=5672
# netstat -punt | grep -s $AMQP_PORT | grep -s $(pgrep -f /usr/bin/nova-consoleauth)
```

The expected output shows the ESTABILISHED connections:

tcp	0	0 192.168.22.205:43638	192.168.22.68:5672	ESTABLISHED 23532/python
tcp	0	0 192.168.22.205:52524	192.168.22.68:5672	ESTABLISHED 23532/python
tcp	0	0 192.168.22.205:52696	192.168.22.68:5672	ESTABLISHED 23532/python
tcp	0	0 192.168.22.205:53833	192.168.22.68:5672	ESTABLISHED 23532/python

6. Verify the process "nova-novnc" is running and listening on its port (default is 6080):

```
# netstat -a | grep -s 6080
```





Allegato Manuale di Installazio

Ver.

The expected output is like the following:

tcp 0 0 preprod-01.ba.infn:6080 *:*	
-------------------------------------	--





	Allegato	Manuale	di	Installazione
--	----------	---------	----	---------------

Ver.

4. Verify the Block Storage Service (Cinder)

Preparation:

Set your --os-* variables in your environment:

\$ source admin-openrc.sh

The following steps allow to verify the correct installation of the Openstack Block Storage Service:

1. Verify that all cinder processes are up and running:

\$ for s in /etc/init.d/cinder-*; do status \$(basename \$s); done

The expected output is like the following:

cinder-api start/running, process 30050
cinder-scheduler start/running, process 30087
cinder-volume start/running, process 30127

If one or more of the above processes are stopped, look at the log files in the folder /var/log/cinder in order to find the problem. Note: depending on your installation, the cinder-volume process may not be running on the controller node (if you have decided to deploy it on a dedicated host, you should check its status there: ssh <cinder-host> service cinder-volume status).

7. Verify the process "cinder-scheduler" is running and connected to the database and messaging server (AMQP):





Allegato Manuale di Installazione

Ver.

a. Verify the connection with the database (replace the DB_PORT value with the correct value depending on your installation. Default is 3306)

```
# export DB_PORT=3306
# netstat -punt | grep -s $DB_PORT | grep -s $(pgrep -f /usr/bin/cinder-scheduler)
```

The expected output shows the ESTABILISHED connections:

tcp	0	0 192.168.22.205:45718	192.168.205.99:33306	ESTABLISHED 23943/python
tcp	0	0 192.168.22.205:45812	192.168.205.99:33306	ESTABLISHED 23943/python

b. Verify the connection with the messaging server (replace the AMQP_PORT value with the correct value depending on your installation. Default is 5672)

```
# export AMQP_PORT=5672
# netstat -punt | grep -s $AMQP_PORT | grep -s $(pgrep -f /usr/bin/cinder-scheduler)
```

The expected output shows the ESTABILISHED connections:

tcp	0	0 192.168.22.205:52528	192.168.22.68:5672	ESTABLISHED 23943/python
tcp	0	0 192.168.22.205:53220	192.168.22.68:5672	ESTABLISHED 23943/python





Allegato	Manuale	di Installazione	
----------	---------	------------------	--

Ver.

8. Finally, to verify that cinder is configured properly, create a new volume:

\$ cinder create --display-name test 1

The expected output is like the following:

+		+-		_+
	Property	· 	Value	
	attachments		[]	
	availability_zone		nova	
1	bootable		false	
1	created_at		2014-06-22T01:14:02.705154	
1	display_description		None	
1	display_name		test	
1	encrypted		False	
1	id		ad2f9004-3939-4b1c-a234-8ab26b8fe961	
	metadata		{}	
	size		1	





Allegato Manuale di Installazion	azione	talla	Ins	di	anuale	Ma	ato	lled	Α
----------------------------------	--------	-------	-----	----	--------	----	-----	------	---

Ver.

	snapshot_id		None		
I	source_volid		None		
	status		creating		
1	volume_type		None		
+		+		+	

9. Check the volume status using the command "cinder list". The status should pass from "creating" to "available":

\$ cinder list

The expected output is like the following:

+		++	+		+	+-		
+								
ID	Status	Display Name	Size	Volume	Type Boo	table	l Attac	rhed
' .	Deacus	Dispidy Name	1 5126	VOTUME	Type Boo	CUDIC	Mccac	Jiica
to								
+		++	+		+	+		
+								
ad2f9004-3939-4b1c-a234-8ab26b8fe961	available	test	1		None	I	false	
		'	'	'				
cfe55712-5933-42fe-b9a2-aacaa8620cd6	creating	test	1	.	None	I	false	
	,	•	,			·		





Allegato Manuale di Installazione

v ei				

+	+	+	
+			

If the status value is not available, the volume creation failed. Check the log files in the /var/log/cinder/ directory on the controller and volume nodes to get information about the failure.





Allea	ato N	/lanuale	di	Install	azione

١	٧	е	r

5. Verify the Networking Service (Neutron)

Preparation:

Set your --os-* variables in your environment:

```
$ source admin-openrc.sh
```

The following steps allow to verify the correct installation of the Openstack Networking Service. In this guide we assume that the networking services have been deployed onto a dedicated node (network node); therefore the following commands should be issued on the network node.

1. Verify that all neutron processes are up and running:

```
$ for s in /etc/init.d/neutron-*; do status $(basename $s); done
```

The expected output is like the following:

```
neutron-dhcp-agent start/running, process 7515

neutron-l3-agent start/running, process 7529

neutron-metadata-agent start/running, process 7537

neutron-ovs-cleanup start/running

neutron-plugin-openvswitch-agent start/running, process 7812

neutron-server start/running, process 7820
```

If one or more of the above processes are stopped, look at the log files in the folder /var/log/neutron in order to find the problem.





Allegato Manuale di Installazione

Ver

2. Query the neutron API to get the list of networks:

```
$ neutron net-list
```

The expected output shows the list of the available networks (if any).

- 3. Verify the process "neutron-dhcp-agent" is running and connected to the messaging server (AMQP):
 - a. replace the AMQP PORT value with the correct value depending on your installation. Default is 5672

```
# export AMQP_PORT=5672
# netstat -punt | grep -s $AMQP_PORT | grep -s $(pgrep -f /usr/bin/neutron-dhcp-agent)
```

The expected output shows the ESTABILISHED connections:

tcp	0	0 192.168.22.218:47911	192.168.22.68:5672	ESTABLISHED 14058/python	
tcp	0	0 192.168.22.218:47912	192.168.22.68:5672	ESTABLISHED 14058/python	
tcp	0	0 192.168.22.218:47910	192.168.22.68:5672	ESTABLISHED 14058/python	

- 4. Verify the process "neutron-I3-agent" is running and connected to the messaging server (AMQP):
 - b. replace the AMQP PORT value with the correct value depending on your installation. Default is 5672

```
# export AMQP_PORT=5672
```





Allegato Manuale di Installazione

Ver.

<pre># netstat -punt grep -s \$AMQP_PORT</pre>	grep -s \$(pgrep -f /usr/bin/neutron-13-agent)	
--	--	--

The expected output shows the ESTABILISHED connections:

tcp	0	0 192.168.22.218:46892	192.168.22.69:5672	ESTABLISHED 9986/python
tcp	0	0 192.168.22.218:47843	192.168.22.68:5672	ESTABLISHED 9986/python
tcp	0	0 192.168.22.218:46891	192.168.22.69:5672	ESTABLISHED 9986/python





Allegato Manuale di Installazion	Allegato Mar	nuale di	Install	azione
----------------------------------	--------------	----------	---------	--------

Ver.

6. Verify the services on the Compute Nodes

Check that the compute and networking agents are up and running and able to communicate with the controller. Use the commands "nova service-list" and "neutron agent-list" (they can be issued from the controller node).

1. Load the admin credentials:

```
$ source admin-openrc.sh
```

2. verify that all the compute nodes are up:

```
$ nova service-list | grep nova-compute
```

nova-compute	preprod-05 nova	enabled up	2014-11-10T12:30:30.000000 None	
nova-compute	preprod-03 nova	enabled up	2014-11-17T15:49:45.000000 None	1
nova-compute	preprod-04 nova	enabled up	2014-11-17T22:48:51.000000 None	

3. verify that the neutron open-vswitch agent is running on the compute nodes:

```
$ neutron agent-list | grep vSwitch
```

The output shows ":-)" if the service is working fine or "xxx" if there are problems

156c3	d5-f685-450a-8fef-1bf9ca3c1e0f	Open	vSwitch	agent	preprod-05	:-)	True		
30fac	bc-7ae5-4f84-b11c-b8908544c7af	Open	vSwitch	agent	preprod-04	:-)	True	1	





Allegato Manuale di Installazione

df7f0820-24d1-41e6-82db-fec1e3296af5 Open vSwitch agent preprod-03 :-)	True	
ed2a74b3-f246-44dd-a3f4-d1170e30b3c0 Open vSwitch agent preprod-02 :-)	True	I





Ver.

7. End-to-End test: VM instantiation

The following bash script can be used to check that the installed Openstack infrastructure is able to provide running virtual machines.

To execute the script you must fill the variables at the beginning of the file with proper values depending on your installation.

IMAGE_ID

To set the IMAGE_ID variable you can use the command "glance image-list" to list the available image ids.

FLAVOR ID

To set the FLAVOR variable you can use the command "nova flavor-list" to list the available flavors (both the flavor name and id can be used).

KEY_NAME

To set the KEY_NAME variable you can use the command "nova keypair-list" to list the available keypairs

NET_ID

To set the NET_ID variable you can use the command "neutron net-list" to list the available networks.

#!/bin/bash

BEFORE RUNNING THIS SCRIPT FILL THE

FOLLOWING VARIABLES WITH PROPER VALUES





Allegato Manuale di Installazione

```
export OS USERNAME=admin
export OS PASSWORD=<password>
export OS TENANT NAME=admin
export OS AUTH URL=http://<controller ip>:35357/v2.0
export IMAGE ID=<image id>
export FLAVOR=<flavor id or name>
export KEY NAME=<key name>
export NET ID=<network id>
LOOP_THRESH=5
WAIT_TIMEOUT=30
wait_vm_active()
   typeset vmid=$1
   let i=0
   status=
```





Allegato Manuale di Installazione

```
while [ $i -lt $LOOP THRESH -a "$status" != active ]
    do
        let i++
        status=$(nova show $vmid | awk '/OS-EXT-STS:vm state/{print $4}')
        echo "VM status is <$status>"
        [ "$status" = active ] && continue
        sleep 30
    done
    [ "$status" = active ]
###########################
### MAIN
#########################
if [ $# -ne 0 ]; then
      echo "Usage: ./`basename $0`"
      echo -e "\nThis probe tries to create a new VM.\nExit code: 0 - probe successfully run (vm is active); 1 - probe
failed"
```





Allegato Manuale di Installazione

```
exit 1
fi
#create the test VM
VM ID=$(nova boot --image $IMAGE ID --key-name $KEY NAME --flavor $FLAVOR --nic net-id=$NET ID test-vm | sed -n 's/^|\
+id \ +| \ +|([^\ ].*\) \ +|/\1/p')
echo "VM id is <$VM ID>"
# wait for vm to become active
wait vm active $VM ID
# check status
if [ $? -ne 0 ]; then
      echo "Error: instance not running after $LOOP_THRESH x $WAIT_TIMEOUT [sec]"
      exit_code=1
else
      echo "OK. VM creation was successful"
      exit code=0
fi
```





Allegato Manuale di Installazione

Ver.

terminate instance

nova delete \$VM_ID

#return 0 if test is ok, 1 otherwise

exit \$exit_code